Item No.	Description of work	No.	Rate	Contents	Rate to be quoted
			Rs. a. p.		Rs.
15	Teakwood ventilators	S.ft.	0 10 0	96	
16	Carting old trusses from old buildings and fixing	Each	10 0 0	4	
17	Purchasing and fixing steel girders	Cwts.	13 0 0	17½	
18	Teakwood wrought and put up (Mysore teak)	C.ft.	4 8 0	85	
19	Carting old wood with cutting, plaining and fixing	,,	2 0 0	42	
20	Roofing with 1st class mangalore tiles on teak reepers including fixing	Sqr.	22 0 0	12.20	
21	Roofing with old tiles and reepers with carting and fixing	,,	8 0 0	6.00	
22	Providing new ridge tiles and cement pointing	R.ft.	0 8 0	71	
23	Fixing old ridge tiles including cement pointing	,,	0 3 0	35	
24	Providing new teakwood eave-board	R.ft.	0 8 0	136	
25	Providing teakwood finials and pendents	Each	1 8 0	6	
26	R. C. roofing with 2 courses of flat tiles and top and bottom plastering, etc., complete	Sqr.	75 0 0	5.40	
27	Plain cornice with brick work including plastering	R.ft.	0 4 0	72	
28	Plain parapet wall including plastering, etc., complete (2′ high)	R.ft.	1 0 0	72	
29	Mortar plastering	Sqr.	3 0 0	47.70	
30	Flooring with cement concrete of 1½″ over 3″ of lime mortar concrete finished with red oxide etc., complete	,,	22 0 0	13.60	
31	Wax polishing to flooring	,,	3 0 0	13.60	
32	Lac Factory green painting	,,	4 8 0	12.00	
33	Wood oiling, etc.	,,	2 0 0	9.10	
34	Preparing and fixing teak wood wall almirahs with wire gauge shutters	S.ft.	1 0 0	108	
35	Teakwood planks for shelves	,,	0 10 0	78	
36	Teakwood shelf pegs fixed in the wall	Each	1 0 0	24	
37	Supplying, fixing new teakwood trellies	S.ft.	0 12 0	300	
38	Supplying new teakwood reepers 2″×1″ plained ready for fixing roofing	100R.ft.	4 8 0	1,000	
39	Lime mortar concrete of granite jelly	C.ft.	0 3 0	400	

B. R. GARUDACHAR,
Executive Engineer.

BANGALORE DIVISION

Abstract Notification dated 10th March 1938.

The attention of the public is hereby invited to the detailed Notification inviting tenders for improving the Industrial School at Chennapatna published on pages 381-386, Part VI of the *Mysore Gazette* dated 17th March 1938. The last date for the receipt of the tender is 2 P.M. on 4th April 1938 and the tender should accompany with a duplicate challan for having credited the deposit amount of Rs. 440 into the Treasury under 17. (*a*) P. W. Deposits.

Notification dated 16th March 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P. M. on 4th April 1938, for widening and deepening the existing well in the silk farm at Chennapatna. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a challan for having credited the deposit amount of rupees two hundred into the treasury under 17(a) P. W. Deposits or in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for widening and deepening the existing well in the Silk Farm at Chennapatna" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, after depositing an additional sum of Rs. 200, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities of work required for widening and deepening the existing well in the Silk Farm Garden in Chennapatna.

No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
				Rs. a. p.	Rs.	Rs.
1	First footing cheltu soil mixed with soft rock including lift and lead 100 feet, from 20 to 30 feet depth	C.yd.	60	2 8 0		
2	Second footing soft rock to be blasted with gun powder with lift and lead 100 feet, 30 to 40 feet depth, ...	,,	154	5 0 0		
3	Third footing hard rock blasting by dynamite with lift and lead 100 feet from 40 to 50 feet depth	,,	52½	23 0 0		
4	Size stone steining for the well above soft rock	C.ft.	4,714	0 2 6		
5	Burnt stone slab bond over revetment for every 10 feet height and slab for steps	S.ft.	934	0 4 6		
6	Burnt stone in mortar, parapet wall around faces roughly dressed ..	C.ft.	376	0 4 6		
7	Providing and fixing burnt stone slab pillars 6″ thick with notches at top roughly dressed	S.ft.	40	0 6 0		
8	Providing and fixing 3″×3″ rolled steel girders weighing 11 lbs. per running-foot including painting, etc.	Cwt.	6	10 8 0		
9	Providing and fixing pulleys	Each	2	2 8 0		

Notification dated 16th March 1938.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 5th April 1938, for Raising the waste weir of Maralwady Tank, Kankanhalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a duplicate challan for having credited the deposit amount of Rs. 175 into the treasury under 17 (a) P. W. Deposits as earnest money, and be superscribed "Tender for Raising the waste weir of Maralwady Tank, Kankanhalli Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, after depositing an additional sum of Rs. 175, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.

Approximate quantities required for raising the wasteweir of Maralwady Tank, Kankanhalli Taluk from R. L. 362.00 to R. L. 365.00.

No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
				Rs. a. p.	Rs.	Rs.
1	Clearing masonry joints chiselling and washing the surfaces before starting the work	Sqr.	22.80	2 0 0		
2	Size stone in surki mortar faces, hammer dressed with bond stones at 6 feet apart in each layer	C.ft.	4,960	0 6 0		
3	Burnt stone slabs 6" thick, one line dressed 6¼' long each set in surki mortar ..	S.ft.	1,950	0 6 0		
4	Cement pointing 1½" deep, 1 cement : 3 sand	Sqr.	47.18	6 0 0		
5	Burnt stone jelly concrete in cement 1 : 2 : : 3. cement sand and jelly 1" cube for the ogee and finishing smooth with cement mortar ½" thick	C.ft.	387	1 0 0		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.